

TYPE OF PROJECT	POUNDS PER SQUARE FOOT	PER 5,000 SQ FT PROJECT	
		POUNDS	TONS
Residential Construction	4.38	21,900	10.95
Nonresidential Construction	4.02	20,100	10.05
Residential Demolition (Single-Family)	111.3	556,500	278.25
Residential Demolition (Multi-Family)	127	635,000	317.5
Nonresidential Demolition	155	775,000	387.5
Nonresidential Renovation	17.7	88,500	44.25
Residential Renovation	Varies by Project	N/A	N/A

Typical Debris Generated by New Residential Construction

DEBRIS TYPE	PERCENT
Wood	42.4%
Drywall	27.3%
Concrete	12.0%
Brick & Other Mixed Debris	7.3%
Cardboard	5.4%
Metals	1.8%
Asphalt	1.4%
Plastics & Foam	1.4%
Other Packaging	0.6%
Textiles	0.4%
TOTAL	100%